Location: 19.0.1C Date: 09-27-2024

Contract:

SN:

Engineer: Study Case: LF Revision: Base

Filename: project-final Config.: Normal

Electrical Transient Analyzer Program

Load Flow Analysis

Loading Category (1): Design

Generation Category (1): Design

Load Diversity Factor: None

	Swing	V-Control	Load	Total
Number of Buses:	1	0	4	5
				Line/Cable/
	XFMR2	XFMR3	Reactor	Busway

Method of Solution: Adaptive Newton-Raphson Method

0

Maximum No. of Iteration: 99

Number of Branches:

Precision of Solution: 0.0001000

System Frequency: 60.00 Hz

Unit System: English

Project Filename: project-final

Output Filename: E:\MIST projects\Level 3-1\Power system project\Untitled.lfr

Project: ETAP Page: 2 19.0.1C Location: Date: 09-27-2024 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: project-final Normal

Adjustments

Tolerance	Apply Adjustments	Individual /Global	Percent
Transformer Impedance:	Yes	Individual	
Reactor Impedance:	Yes	Individual	
Overload Heater Resistance:	No		
Transmission Line Length:	No		
Cable / Busway Length:	No		
Temperature Correction	Apply Adjustments	Individual /Global	Degree C
Transmission Line Resistance:	Yes	Individual	
Cable / Busway Resistance:	Yes	Individual	

Location: 19.0.1C Date: 09-27-2024

Contract:

Engineer:

Revision:

SN:

Base

Filename: Study Case: LF

Study Case: LF

Config.: Normal

Bus Input Data

						Load						
Bus		Initial Voltage		Constant kVA		Constant Z		Constant I		Generic		
ID	kV	Sub-sys	% Mag.	Ang.	MW	Mvar	MW	Mvar	MW	Mvar	MW	Mvar
Bus1	10.600	1	100.0	0.0								
Bus2	10.000	1	100.0	0.0	20.000	10.000						
Bus3	10.000	1	100.0	0.0	45.000	15.000						
Bus4	10.000	1	100.0	0.0	40.000	5.000						
Bus5	10.000	1	100.0	0.0	60.000	10.000						
Total Number of Buses: 5					165.000	40.000	0.000	0.000	0.000	0.000	0.000	0.000

Generation Bus			Voltage			Generation	Mvar Limits				
ID	kV	Туре	Sub-sys	% Mag.	Angle	MW	Mvar	% PF	Max	Min	
Bus1	10.600	Swing	1	100.0	0.0						_
Bus2	10.000	Mvar/PF Control	1	100.0	0.0	40.000	30.000	80.0			
						40.000	30.000				

Project: ETAP Page: 4 19.0.1C Location: Date: 09-27-2024 SN: Contract: Engineer: Revision: Base Study Case: LF Config.: Filename: project-final Normal

Impedance Input Data

Impedance	Positive S	Sequence Im	pedance	
ID	R	X	Y	Unit
1-2	2	6	6	% in 10.000 kV base and 100.0 MVA base
1-3	8	24	5	% in 10.000 kV base and 100.0 MVA base
2-3	6	25	4	% in 10.000 kV base and 100.0 MVA base
2-4	6	18	4	% in 10.000 kV base and 100.0 MVA base
2-5	4	12	3	% in 10.000 kV base and 100.0 MVA base
3-4	1	3	2	% in 10.000 kV base and 100.0 MVA base
4-5	8	24	5	% in 10.000 kV base and 100.0 MVA base

Location: 19.0.1C Date: 09-27-2024

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: project-final Config.: Normal

Branch Connections

CKT	/Branch	Col	nnected Bus ID	% Impe	% Impedance, Pos. Seq., 100 MVA Base						
ID	Туре	From Bus	To Bus	R	X	Z	Y				
1-2	Impedance	Bus1	Bus2	1.78	5.34	5.63	6.7416010				
1-3	Impedance	Bus1	Bus3	7.12	21.36	22.52	5.6180010				
2-3	Impedance	Bus3	Bus2	5.34	22.25	22.88	4.4944010				
2-4	Impedance	Bus4	Bus2	5.34	16.02	16.89	4.4944010				
2-5	Impedance	Bus2	Bus5	3.56	10.68	11.26	3.3708000				
3-4	Impedance	Bus3	Bus4	0.89	2.67	2.81	2.2472000				
4-5	Impedance	Bus4	Bus5	7.12	21.36	22.52	5.6180010				

Location: 19.0.1C Date: 09-27-2024

SN:

Contract:

Engineer: Study Case: LF Revision: Base

Filename: project-final Config.: Normal

LOAD FLOW REPORT

	Bus		Volt	age	Gener	ation	Lo	ad		Load Flow				XFMR
I	D	kV	% Mag.	Ang.	MW	Mvar	MW	Mvar	ID	MW	Mvar	Amp	%PF	%Тар
* Bus1		10.600	100.000	0.0	129.612	-7.048	0.000	0.000	Bus2	87.223	-8.364	4772.6	-99.5	
									Bus3	42.389	1.316	2309.9	100.0	
Bus2		10.000	104.758	-2.8	40.000	30.000	20.000	10.000	Bus1	-85.864	5.777	4742.9	-99.8	
									Bus3	19.802	3.791	1111.2	98.2	
									Bus4	30.132	3.011	1668.9	99.5	
									Bus5	55.930	7.422	3109.5	99.1	
Bus3		10.000	102.289	-5.2	0.000	0.000	45.000	15.000	Bus1	-41.097	-2.867	2325.3	99.8	
									Bus2	-19.568	-7.103	1175.0	94.0	
									Bus4	15.666	-5.030	928.7	-95.2	
Bus4		10.000	102.254	-5.5	0.000	0.000	40.000	5.000	Bus2	-29.621	-5.763	1703.8	98.2	
									Bus3	-15.641	3.013	899.3	-98.2	
									Bus5	5.261	-2.250	323.1	-91.9	
Bus5		10.000	101.764	-6.2	0.000	0.000	60.000	10.000	Bus2	-54.760	-7.111	3132.8	99.2	
									Bus4	-5.240	-2.889	339.5	87.6	

^{*} Indicates a voltage regulated bus (voltage controlled or swing type machine connected to it)

[#] Indicates a bus with a load mismatch of more than 0.1 MVA

Location: 19.0.1C Date: 09-27-2024

Contract:

SN:

Engineer: Study Case: LF Revision: Base

Filename: project-final Config.: Normal

Bus Loading Summary Report

Directly Connected Load Total Bus Load Bus Constant kVA Constant Z Constant I Generic Percent kV MW MW Mvar MW Mvar MW Mvar Mvar MVA ID Rated Amp % PF Loading Amp Bus1 10.600 7074.2 129.881 99.8 Bus2 10.000 20.000 10.000 129.390 97.3 7131.1 Bus3 10.000 45.000 15.000 62.492 97.1 3527.3 Bus4 10.000 40.000 5.000 45.965 98.5 2595.3 Bus5 10.000 60.000 10.000 60.828 98.6 3451.0

^{*} Indicates operating load of a bus exceeds the bus critical limit (100.0% of the Continuous Ampere rating).

[#] Indicates operating load of a bus exceeds the bus marginal limit (95.0% of the Continuous Ampere rating).

Project:		ETAP	Page:	8
Location:		19.0.1C	Date:	09-27-2024
Contract:			SN:	
Engineer:		Study Case: LF	Revision:	Base
Filename:	project-final	Suray Suse. 21	Config.:	Normal

Branch Losses Summary Report

	From-To	Bus Flow	To-From	Bus Flow	Los	ses	% Bus V	Voltage	Vd % Drop
Branch ID	MW	Mvar	MW	Mvar	kW	kvar	From	То	in Vmag
1-2	87.223	-8.364	-85.864	5.777	1358.6	-2587.2	100.0	104.8	1.17
1-3	42.389	1.316	-41.097	-2.867	1291.4	-1550.4	100.0	102.3	3.50
2-3	19.802	3.791	-19.568	-7.103	234.0	-3312.5	104.8	102.3	2.47
2-4	30.132	3.011	-29.621	-5.763	511.2	-2752.4	104.8	102.3	2.50
2-5	55.930	7.422	-54.760	-7.111	1170.2	311.0	104.8	101.8	2.99
3-4	15.666	-5.030	-15.641	3.013	25.0	-2017.0	102.3	102.3	0.04
4-5	5.261	-2.250	-5.240	-2.889	21.3	-5139.1	102.3	101.8	0.49
					4611.7	-17047.7			

^{*} This Transmission Line includes Series Capacitor.

Location: 19.0.1C Date: 09-27-2024

SN:

Base

Engineer: Study Case: LF Revision:

Contract:

Filename: project-final Config.: Normal

Alert Summary Report

% Alert Settings

	Critical	Marginal
Loading		
Bus	100.0	95.0
Cable / Busway	100.0	95.0
Reactor	100.0	95.0
Line	100.0	95.0
Transformer	100.0	95.0
Panel	100.0	95.0
Protective Device	100.0	95.0
Generator	100.0	95.0
Inverter/Charger	100.0	95.0
Bus Voltage		
OverVoltage	105.0	102.0
UnderVoltage	95.0	98.0
Generator Excitation		
OverExcited (Q Max.)	100.0	95.0
UnderExcited (Q Min.)	100.0	

Critical Report

Devi	ce ID	Type	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type	
Gen2		Generator	Overload	40.000	MW	40.000	100.0	3-Phase	
Gen2		Generator	Over Excited	24.790	Mvar	30.000	121.0	3-Phase	
Gen6		Generator	Under Excited	0.000	Mvar	-7.048	0.0	3-Phase	

Marginal Report

Device ID	Туре	Condition	Rating/Limit	Unit	Operating	% Operating	Phase Type
Bus2	Bus	Over Voltage	10.000	kV	10.476	104.8	3-Phase
Bus3	Bus	Over Voltage	10.000	kV	10.229	102.3	3-Phase
Bus4	Bus	Over Voltage	10.000	kV	10.225	102.3	3-Phase

Project: ETAP Page: 10 19.0.1C Location: Date: 09-27-2024 SN: Contract: Engineer: Revision: Base Study Case: LF Filename: Config.: project-final Normal

SUMMARY OF TOTAL GENERATION, LOADING & DEMAND

	MW	Mvar	MVA	% PF
Source (Swing Buses):	129.612	-7.048	129.803	99.85 Leading
Source (Non-Swing Buses):	40.000	30.000	50.000	80.00 Lagging
Total Demand:	169.612	22.952	171.158	99.10 Lagging
Total Motor Load:	165.000	40.000	169.779	97.19 Lagging
Total Static Load:	0.000	0.000	0.000	
Total Constant I Load:	0.000	0.000	0.000	
Total Generic Load:	0.000	0.000	0.000	
Apparent Losses:	4.612	-17.048		
System Mismatch:	0.000	0.000		

Number of Iterations: 4